High gradient multi-cell R&D in 2003/2004

Lutz Lilje MPY 21.1.2004

- EP setup at DESY commissioned
- First DESY EP cavity: 39 MV/m at 2K
- Overview on EP statistics
- 2 cavities with KEK EP at 35 MV/m in high power test (AC72,AC73)
- Proposal for future work
 - EP
 - CHECHIA tests



35 MV/m for 800 GeV c.m.



Electrolytic Polishing at DESY

Infrastructure for 9-cell cavities was commissioned with single cell cavities.

9-cell cavities will follow soon.



Recent test DESY EP cavity


- EP system is working
- Fine-tuning has started
- First two cavity tests were only partially successful
 - defect not fully removed (AC78)
 - Q-disease due to unclear history (P-1)



History on AC70

- Only 800°C firing
- EP at KEK/Nomura (100+50um): Strong field emission (FE)
- BCP (8+10um) to try to remove FE: not successful
- EP@DESY (~40um) : 30 MV/m with Qslope
- Baking







Typical behaviour after 124°C bake


Lutz Lilje DESY






AC70: History






Limitation of EP nine-cells



Comparison of heat treatments in EP cavities



EP and heat treatments

Batch of cavities	$800^{\circ}\mathrm{C}$	$1400^{\circ}\mathrm{C}$
single-cells	35.4 ± 5.3	34.7 ± 2.5
nine-cells	34.0 ± 3.9	33.0 ± 3.3
single cell analysis of	35.6 ± 2.8	35.6 ± 1.7
nine-cell cavities		



26/01/2004

High-power Test of Cavities AC72 and AC73 in CHECHIA (Horizontal cryostat)



Lutz Lilje DESY




Coupler processing in High Power tests

- Coupler and cavity processing went smoothly
 - RF on time for full warm conditioning <90 hours
 - coupler heating to 150°C
 - full warm and cold processing



Warm processing of the coupler




Multipacting

- Cavity AC72 has shown multipacting similar to AC73
- resonant electron emission results in an avalanche
- Xray emission at power levels corresponding to 20 MV/m disappeared after processing for a few hours (see below)
- barrier is soft:
 - when the cavity is kept below 100 K no new processing necessary
 - after warmup very short processing is needed (some minutes)




Multipacting also in AC72?




Lutz Lilje DESY



26/01/2004



High Power Test of AC72




Cavity AC72 performance measurements

- 35 MV/m at ~6,5*10⁹ (10 Hz)
- 34,7 MV/m at ~9*10⁹ (1 Hz)
- Problems with HOM #2
 - no Piezo compensation
 - no LLRF feedback, but
 - much lower noise on LLRF signals (as compared with AC73 test)
 - LLRF for lower gradient o.k (adaptive feedforward)



High Power Test of AC73




Some statistics on the test


- Test running 7.3.2003 14.8.2003
 - test took about 160 days (exact 3848 hours)
 - Scheduled cryo shutdown about 600 hours
 - warm-ups: 2x300 K, 4-5 times around 100 K
- Processing took about 165 hours
 - coupler 130 hours
 - cavity 35 hours

- RF operation of the coupler
 - cavity off-resonance and not at 2 K
 - power between 150 600 kW
 - 5 Hz operation very smooth
 - 10 Hz causes heating of the warm ceramics
 - Total time RF on ~ 2400 hours
- RF operation of the cavity
 - 1100 hours at around 35 +/-1 MV/m
 - ~110 hours without interruption
 - 57 hours at 36 MV/m +
 - most of this is feed-forward operation
- Piezo compensation
 - about 700 hours






Drawing of current setup (H.-B. Peters)




RF signals at 35 MV/m




Frequency stabilization during RF pulse using a piezoelectric tuner Blue: With piezo


Red: Without piezo

Frequency detuning of 500 Hz compensated voltage pulse (~100 V) on the piezo. No resonant compensation



Piezo excitation of the cavity for frequency compensation (operation for 700 hours)





Damping of the ringing between pulses (5Hz operation)

Plans for 2004

- Cavities
 - Rework (Re-EP) the existing cavities from the AC series, then continue with ZANON production
 - Accumulate as much experience as possible with EP
 - First 10 ZANON cavities will not get 1400°C
 - Should be possible to get around 8 cavities for a module by september this year
 - Look at possible promising cavities from older productions: A16
 - Further CHECHIA tests
 - AC70,...
 - More experience on assembly of tank and high power coupler
 - Piezo tuner needs engineering design and tests
 - Try to get about 8 CHECHIA tests until the end of the year



Plans for 2004

- Assembly of the Module of type II
 - Should aim at 35 MV/m
 - Can serve as a spare module
 - This could use AC73 as Cavity #1 (Fermilab option!?)
- Options for module type I spare
 - Rework old cavities from module 2
 - Need flange modification (Nb->NbTi)
 - Only etch is possible (nobody has tried EP on cavities with tank)
 - Block the infrastructure for a significant time (No EP, no preparation for CHEHCIA)
 - Continue EP on ZANON series
 - built new tanks of the old type
 - Needs check with schedule, available manpower
 - Requires money for tank preparation and welding

Lutz Lilje DESY



26/01/2004

Options for module tests

- Difficult to guess
- According to today's planning
 - LINAC
 - Installation not before 2005
 - Cooldown not before 2006
 - Module test stand
 - When money becomes available, ~1 1/2 year later first test



Conclusion

- DESY EP cavity reaches 39 MV/m at 2K
- Not a big difference between 800°C and 1400°C firing
- Two electropolished nine-cell cavities have performed at very high gradients and sufficiently high Q fulfilling TESLA-800 specification in high power test
- Couplers performed very well, no problems
- The piezo proof-of-principle at 35 MV/m exists

