JRA1 start up meeting WP 3, Seamless Cavity Production W- D. Möller, DESY

- WP1 follows the idea to fabricate the actual cavity (excluding the end groups with auxiliary components like input coupler ports, higher order mode dampers...) by a method that avoids welding.
- This would eliminate possible performance degradation by a low quality weld.
- There are two methods of seamless production: spinning and hydro-forming.
- Very encouraging results are obtained with single cell cavities.
- This technology will be extended to multi-cell cavities.





Deliverables for WP3

- spinning
 - Design, commissioning and operation of a machine for spinning multicell cavities
 - Deliverables: Description of optimum parameters for spinning and production of prototypes Seamless cavity production by hydroforming
- hydroforming
 - Design, commissioning and operation of a machine for hydroforming of multicell cavities.
 - Deliverables: Description of optimum parameters for hydroforming and production of prototypes





Time Schedule for the next 18 Month

				2004	2005		
Task Name	Milestones	Deliverables	12	01 02 03 04 05 06 07 08 09	10 11 12	01 02 03 04 05 0	6 07 08 09
WP3 Seamless cavity production							
3.1 Seamless by spinning			•				•
3.1.1 Design spinning machine			•	·			
3.1.1.1 Drawings of the matrices			1				
3.1.1.2 Drawings of the support system			1	h h			
3.1.1.3 Design finished	Design fin ished		1	▶	17/09		
3.1.2 Construction of spinning machine			1	-			•
3.1.2.1 fabrication of machine parts			1	l l			
3.1.2.2 Software for the machine			1	l l b		-	
3.1.2.3 assembly of machine			1				
3.1.2.4 Commissioning of the machine			1				
3.2 Seamless by hydroforming			•				•
3.2.1 Design hydro for ming machine			•				
3.2.1.1 Drawings of the matrices			1				
3.2.1.2 Drawings of the support system			1	E F			
3.2.1.3 Design finished	Design report		1	₩	17/09		
3.2.2 Construction of hydroforming machine			•				•
3.2.2.1 Hydraulic for machine			1				
3.2.2.2 Software for the machine			1				
3.2.2.3 Machine fabrication			1				
3.2.2.4 Commissioning of the machine			1				-
3.2.2.5 Commissioning finished	Hydroforming machine ready		1			[\$ 30/06
3.2.3 Construction of tube necking machine] •				
3.2.3.1 Drawings of the support system and turning mechanism							
3.2.3.2 Drawings of the necking mechanism			1	F.			
3.2.3.3 Construction of the tube necking machine			1				
3.2.3.4 Software for the tube necking machine			1			n 🗂	
3.2.3.5 Necking machine ready	Necking machine ready		1			24/02	
3.2.4 Development of seamless tubes for 9-cell cavities			•	·			•
3.2.4.1 Fabrication and inspection of bulk Nb test tubes							
3.2.4.2 Fabrication and inspection of bimetallic NbCu test tubes							
3.2.4.3 Seamless tubes ready	Prototypes of tubes finished		1			l t	\$ 30/06





JRA1 WP3 Task 3.1 Seamless cavity production by spinning.

Enzo Palmeri







What we plan to do is to modify a standard spinning lathe in order to have a machine peculiar for 9-cells



A standard machine will be adapted by increasing the pressure between headstock and tailstock; a second roller tower will be added if it will be not possible to make the roller pushing also backward

Scientific Programme:

Pre-Industrialization of the spinning technique by:

- Construction of other 9-cell prototypes with an improved internal finishing after forming.
- Reduction of spinning time

JRA1 WP3 Task 3.2 Seamless cavity production by hydroforming.

W. Singer

Necking machine: new PC controlled necking procedure with profile ring.



Necking mechanism.



Principle of tube diameter reduction in the iris area

The equipment construction and set up of the parameters, especially regarding iris area, should be done

Hydroforming machine (reconstruction)





Heart of hydroforming machine

Principle of the tube expansion with intermediate matrix

Equipment allowing reliable simultaneous fabrication of three cells Equipment allowing fabrication of any desired number of cells

Fabrication of seamless tubes

Bulk Nb tubes



NbCu bonded tubes

Explosively bonded NbCu tubes

NbCu single cell cavity 1NC2 produced at DESY by hydroforming from explosively bonded tube. Preparation and HF tests at Jeff. Lab: 180 µm BCP, annealing at 800°C, baking at 140°C for 30 hours, HPR.



Hydroformed NbCu clad single cell cavities 1.00E+11 1.00E+10 ရိ 1,00E+09 50 µm, HT 130°C 1NC3. HT 750°C. BCP 1.00E+08 200 µm 0 10 20 30 40 Eacc, MV/m

bonded cavities. Preparation and RF tests at JLab. KEK, DESY

T=2K - M easured after guenches

Experiences: It is difficult to keep the explosive bonding parameters under control.

T=2K

Coextruded NbCu tubes (another fabrication procedure)



Cu-Nb-Cu Sandwiched Tubes (KEK)



Single cell NbCu cavities produced at DESY from KEK sandwiched tube. The best achieved result Eacc = 39MV/m Fabrication principle of sandwiched Cu-Nb-Cu tube

> NSC-3: Barrel polishing, CP(10microns), Annealing 750°C x 3h, EP(70microns) by K.Saito



E_{acc} of best sputtered NbCu cavities is <25 MV/m

Fight against dangerous of cracks in iris area appeared during hydroforming.

The difference in recrystallization temperature of Nb and Cu is significant



Example of cracks at iris area after hydroforming

Microstructure of Cu and Nb after annealing at 560°C for 2 hours. Nb is not recrystallysed.

Possible solution:

using specially dotted Cu with high recrystallization temperature